

(An Autonomous Institution of MNRE, GOI)

19 K.m Stone, Gurgaon-Faridabad Road, Gwal Phari, Gurgaon (Haryana)-122003

File No: 468/2017-18 /CSC/NISE/242Dated: 29/05/18To: M/s- Energetech UPS Pvt. Ltd.Sr. No 399/1-2, Bhave P.O. GhotawadeNear Pirangut, Tal Mulshi, Dist- Pune- 412115Subject: Issue of Test Report by National Institute of Solar Energy ('NISE')

Dear Sir,

Please refer to your letter No./Order Form No. 07 Dated 12/03/18 In this connection, I am directed to enclose herewith the Test Report No. 468/2017-18/CSC/NISE Dated 29/05/18 In respect of your submitted samples in original, for ready reference and record.

2. Discrepancies, if any observed, in respect of any of the entries contained in the above report should be brought to the notice of this office within 30 days from the date of issue of this letter, failing which it will be presumed that the entries therein are in order and no further correspondence will be entertained thereafter on this particular report.
3. We would like to solicit your views and therefore enclosing a Feedback Form with a request to be filled up by you and then send as soon as possible. Your suggestions are valuable for us to make our further improvements and take corrective action in improving our quality of service.
4. Further, You are also requested to collect your samples at your cost within 60 days, from the date of issue of this letter falling which NISE will dispose of the sample in best possible manner and NISE will not be responsible in any manner for this sample.

Kindly acknowledge the receipt of this letter along with original test report and original Invoice.



Yours faithfully

(In-charge, Customer Service Cell)
*National Institute of Solar Energy)

Encl:

1. Test Report-Total Page 15
2. Feedback Form

Copy forwarded for information to:

1. PA to Director General-NISE
2. Guard File
3. Office Copy



National Institute of Solar Energy

(An autonomous Institute of Ministry of New & Renewable Energy)

Gurugram-Faridabad Road, Gwalpahari, Gurugram-122003

Ph. 0124-2579251 (CSC), Fax: 0124-2579207

Email Id: csc.nise.mnre@gmail.com

Test Report

1.	Service Request No.	44/1217
2.	Requested By (Name & Address of the organization)	M/s Eneritech UPS PVT. LTD. Sr. No. 399/1-2, Bhare P.O. Ghotawade Near Pirangut, Tal Mulshi, Dist- Pune -412115
3.	Details of the test item	
	a) Nomenclature	Hybrid type inverter (Battery + PV + Grid Import + Grid Export)
	b) Capacity	20 KVA/20 kW
	c) Manufactured By	M/s Eneritech UPS PVT. LTD.
	d) Model / Type No.	20 kVA/20 kW/240 V
	e) Serial No.	1) 201709296 2) 201709298
	f) Testing procedure	Prototype submitted by the client
	g) Testing parameters	<ul style="list-style-type: none"> ✓ Inverter efficiency test - as per IEC 61683 "Photovoltaic systems -Power conditioners -Procedure for measuring efficiency." ✓ Grid parallel operation test - as per CEI IEC 61727- "Photovoltaic (PV) systems -Characteristics of the utility interface." ✓ Islanding test -as per IEC 62116 "Test procedure of islanding prevention measures for utility-interconnected photovoltaic inverters." ✓ Environmental test as per IEC 60068-2 (1, 2, 14, 30)
6.	Date of Submission of Samples	12/03/2018
7.	The condition of samples on receipt	Good
8.	Date of Completion of Tests	25/05/2018

B. Major equipment USED

S.No.	Equipment Used	Model	Calibration Agency/Report Reference	Last calibration date
1	Solar array simulator	ETS600*25D-PVE	Calibrated from ERTL(N)	05/04/2018
2	Power Analyzer	WT 1800	Calibrated from ERTL(N)	09/04/2018
3	Digital Oscilloscope, Tektronix TDS210	DPO	Calibrated from ERTL(N)	23/03/2018
4	AC power source	61704	Calibrated from ERTL(N)	04/04/2018
5	Anti-Islanding Testing Device	Actual RLC Load 60 KVA	Calibrated from ERTL(N)	05/04/2018

Tested By
Kantesh
Date.....

Authorized Signatory *Rishiwar*
29/05/18
Date.....





Inverter Efficiency Test Result as per IEC-61683 for Hybrid mode (for details, please see Annexure I)			
Cl 4.2	Temperature maintained in the laboratory.	27°C	
Cl 4.3	Output voltage and frequency	230 V and 50Hz	
Cl 4.4	Input voltage	PV (292-397) VMP, battery 240	
Cl 5.1	Rated output efficiency (for details, please see Annexure	given below	
Cl 5.2	Partial output efficiency (for details, please see Annexure	given below	
Efficiency at minimum voltage (292 V)			
	DC input power-PV (%)	Efficiency (%)	Uncertainty (± in %)
Partial output	5	62.14	0.61
	10	78.61	0.59
	25	87.71	0.43
	50	90.59	0.35
	75	89.98	0.14
Rated output	100	89.32	0.15
Efficiency at medium voltage (343 V)			
	DC input power-PV (%)	Efficiency (%)	Uncertainty (± in %)
Partial output	5	53.40	0.75
	10	74.60	0.65
	25	87.86	0.30
	50	89.06	0.16
	75	89.95	0.16
Rated output	100	88.10	0.16
Efficiency at maximum voltage (397 V)			
	DC input power-PV (%)	Efficiency (%)	Uncertainty (± in %)
Partial output	5	44.58	0.50
	10	75.02	0.51
	25	84.16	0.52
	50	87.34	0.19
	75	88.58	0.15
Rated output	100	87.83	0.15

Inverter Efficiency Test Result as per IEC-61683 for Standalone mode (for details, please see Annexure II)			
	Load %	System Efficiency (%) at pf 1	Uncertainty (± in %)
Partial output	5	73.34	0.22
	10	82.07	0.19
	25	90.13	0.14
	50	92.74	0.14
	75	92.67	0.14
Rated output	100	92.24	0.13
	Load %	System Efficiency (%) at pf 0.8	Uncertainty (± in %)
Partial output	5	---	---
	10	---	---
	25	91.18	0.14
	50	89.05	0.17
	75	91.25	0.14
Rated output	100	90.96	0.13

Tested By
Kanlesh
Date.....

Authorized Signatory
R. Jeyakumar
Date..... *29/05/2018*

Issued By
[Signature]
Date.....
*National Institute of Standards and Technology
Berugram*



Islanding prevention measures for utility-interconnected photovoltaic inverters: IEC 62116	
CI 6.2	Pass (for details, please see Annexure III)

Photovoltaic (PV) systems –Characteristics of the utility interface (CEI IEC -61727)	
CI- 4.4,4.5,4.6,4.7,5.3,5.4	Pass (for details please see annexure IV)

Environmental test as per IEC 60068-2 (1, 2, 14, 30)	
Pass (for details please see annexure VI)	

Photographs of the sample (for details, please see Annexure-VII)	
---	--

NOTE:

1. This test report refers only to the particular items submitted for testing as per specifications/requirements stipulated by the customer.
2. The results reported in the Test Report are valid at the time of and under the stipulated conditions of measurements.
3. The test report shall not be reproduced except in full unless written permission for the publication of an approved abstract has been obtained from the Director, National Institute of Solar Energy.
4. The client is requested to collect the tested sample back within 30 days from the date of issue of the report

Kamlesh
Tested By

Date.....

Pooja Lakshmi
29/05/2018

Authorized Signatory

Date.....



Issued By

Date.....

[Signature]



Annexure - I

*Efficiency in Hybrid Mode = Output Power (Battery + Load + Grid Import/Export) / Solar Input

* (-) sign in AC Power: Power import from grid

* (+) sign in AC Power: Power export to grid

Table 1: System efficiency as per IEC 61683 for Hybrid mode at maximum voltage (292 V)							
S.No.	Load %	5	10	25	50	75	100
1.	RMS Voltage 1 (V)	225.38	232.16	227.28	229.27	228.93	228.27
2.	RMS Current 1 (I)	1.66	1.61	4.16	11.01	19.01	24.15
3.	Active Power 1 (P)	195.00	247.00	872.00	2399.00	3976.00	5022.00
4.	Reactive Power 1 (Q)	318.00	279.00	367.00	789.00	1766.00	2272.00
5.	Apparent Power 1 (S)	373.00	373.00	946.00	2525.00	4351.00	5512.00
6.	Power Factor 1 (PF)	0.52	0.66	0.92	0.95	0.91	0.91
7.	Frequency 1 (Hz)	50.01	49.96	50.04	50.01	50.05	49.92
8.	RMS Voltage 2 (V)	224.86	231.52	227.00	230.50	230.88	228.35
9.	RMS Current 2 (I)	1.10	4.16	7.50	16.98	24.65	31.65
10.	Active Power 2 (P)	84.00	892.00	1624.00	3864.00	5555.00	6660.00
11.	Reactive Power 2 (Q)	232.00	366.00	508.00	625.00	1230.00	2805.00
12.	Apparent Power 2 (S)	246.00	964.00	1701.00	3914.00	5690.00	7227.00
13.	Power Factor 2 (PF)	0.34	0.93	0.95	0.99	0.98	0.92
14.	Frequency 2 (Hz)	50.01	49.96	50.04	50.01	50.05	49.92
15.	RMS Voltage 3 (V)	224.28	232.66	226.35	231.42	231.39	227.62
16.	RMS Current 3 (I)	1.81	2.59	7.79	12.43	20.30	31.06
17.	Active Power 3 (P)	161.00	451.00	1682.00	2697.00	4074.00	6169.00
18.	Reactive Power 3 (Q)	372.00	400.00	528.00	996.00	2340.00	3455.00
19.	Apparent Power 3 (S)	405.00	603.00	1763.00	2875.00	4698.00	7071.00
20.	Power Factor 3 (PF)	0.40	0.75	0.95	0.94	0.87	0.87
21.	Frequency 3 (Hz)	50.01	49.96	50.05	50.00	50.05	49.92
22.	Voltage THD 1 (%)	0.99	0.91	1.22	1.35	1.35	1.50
23.	Current THD 1 (%)	39.65	52.09	20.14	11.05	9.20	8.79
24.	Voltage THD 2 (%)	0.99	0.91	1.27	1.38	1.47	1.68
25.	Current THD 2 (%)	63.30	14.40	18.48	9.76	7.05	5.89
26.	Voltage THD 3 (%)	1.24	1.10	1.37	1.72	1.90	2.14
27.	Current THD 3 (%)	42.41	30.54	15.43	7.93	6.62	5.43
28.	PV Voltage (V)	296.65	282.27	297.50	278.45	281.86	286.04
29.	PV Current (I)	3.50	7.10	16.70	35.90	53.30	69.70
30.	Total Input PV Power (W)	1030.00	2010.00	4980.00	9990.00	15020.00	19930.00
31.	Battery Voltage (V)	270.54	265.50	274.55	265.50	262.94	266.27
32.	Battery Current (I)	2.20	0.00	0.70	0.30	0.30	0.20
33.	Input dc Power (W)	590.00	10.00	190.00	90.00	90.00	50.00
34.	Efficiency (%)	62.14	78.61	87.71	90.59	89.98	89.32

Tested By
Kamlesh
Date.....



Issued By *[Signature]*
Date.....



Table 2: System efficiency as per IEC 61683 for Hybrid mode at maximum voltage (343 V)

S.No.	Load %	5	10	25	50	75	100
35.	RMS Voltage 1 (V)	222.67	223.73	223.52	222.85	223.36	223.40
36.	RMS Current 1 (I)	1.62	2.31	3.82	10.28	17.84	25.34
37.	Active Power 1 (P)	87.00	357.00	709.00	2233.00	3775.00	4988.00
38.	Reactive Power 1 (Q)	349.00	375.00	476.00	509.00	1277.00	2679.00
39.	Apparent Power 1 (S)	360.00	517.00	854.00	2291.00	3985.00	5661.00
40.	Power Factor 1 (PF)	0.24	0.69	0.83	0.98	0.95	0.88
41.	Frequency 1 (Hz)	50.00	49.91	49.97	49.90	49.94	49.97
42.	RMS Voltage 2 (V)	221.39	223.95	222.05	222.99	223.97	223.31
43.	RMS Current 2 (I)	1.01	2.40	6.98	14.68	22.89	32.94
44.	Active Power 2 (P)	78.00	433.00	1490.00	3213.00	4873.00	6584.00
45.	Reactive Power 2 (Q)	209.00	316.00	430.00	623.00	1594.00	3279.00
46.	Apparent Power 2 (S)	223.00	536.00	1550.00	3273.00	5128.00	7355.00
47.	Power Factor 2 (PF)	0.35	0.81	0.96	0.98	0.95	0.90
48.	Frequency 2 (Hz)	50.00	49.90	49.97	49.90	49.94	49.96
49.	RMS Voltage 3 (V)	220.80	222.51	221.49	221.63	222.71	222.94
50.	RMS Current 3 (I)	2.27	3.87	9.05	15.96	23.90	31.96
51.	Active Power 3 (P)	403.00	767.00	1936.00	3343.00	4794.00	6040.00
52.	Reactive Power 3 (Q)	297.00	392.00	517.00	1158.00	2311.00	3781.00
53.	Apparent Power 3 (S)	501.00	861.00	2004.00	3537.00	5322.00	7126.00
54.	Power Factor 3 (PF)	0.80	0.89	0.97	0.94	0.90	0.85
55.	Frequency 3 (Hz)	49.99	49.90	49.97	49.90	49.94	49.97
56.	Voltage THD 1 (%)	1.23	1.08	1.48	1.60	1.64	1.69
57.	Current THD 1 (%)	42.63	44.41	22.53	11.79	9.38	8.47
58.	Voltage THD 2 (%)	1.33	1.12	1.51	1.70	1.79	1.90
59.	Current THD 2 (%)	88.12	25.05	19.55	11.40	7.68	6.01
60.	Voltage THD 3 (%)	1.51	1.25	1.66	1.91	2.11	2.36
61.	Current THD 3 (%)	28.75	22.60	14.16	8.63	6.33	5.76
62.	PV Voltage (V)	375.71	298.81	318.17	318.94	323.15	335.23
63.	PV Current (I)	2.70	6.60	15.10	31.20	46.50	59.60
64.	Total Input PV Power (W)	1000.00	1980.00	4820.00	9970.00	15010.00	19980.00
65.	Battery Voltage (V)	269.48	254.14	272.57	256.40	267.28	267.10
66.	Battery Current (I)	0.50	0.30	0.30	0.30	0.20	0.00
67.	Input dc Power (W)	140.00	80.00	100.00	90.00	60.00	10.00
68.	Efficiency (%)	53.40	74.60	87.86	89.06	89.95	88.10

Kamlesh
Tested By

Date.....



Issued By *Shuchi*

Date.....



Table 3: System efficiency as per IEC 61683 for Hybrid mode at maximum voltage (397 V)

S.No.	Load %	5	10	25	50	75	100
69.	RMS Voltage 1 (V)	220.20	221.44	220.95	221.48	221.70	223.70
70.	RMS Current 1 (I)	2.06	3.13	5.78	11.46	20.25	28.19
71.	Active Power 1 (P)	59.00	510.00	1240.00	2433.00	4208.00	5689.00
72.	Reactive Power 1 (Q)	450.00	468.00	310.00	724.00	1565.00	2722.00
73.	Apparent Power 1 (S)	454.00	692.00	1278.00	2539.00	4490.00	6306.00
74.	Power Factor 1 (PF)	0.13	0.74	0.97	0.96	0.94	0.90
75.	Frequency 1 (Hz)	49.93	49.88	49.84	49.87	49.90	49.92
76.	RMS Voltage 2 (V)	219.79	221.32	222.56	223.31	224.07	226.89
77.	RMS Current 2 (I)	1.50	1.76	6.68	14.51	22.05	30.63
78.	Active Power 2 (P)	201.00	242.00	1392.00	3181.00	4624.00	6249.00
79.	Reactive Power 2 (Q)	261.00	304.00	522.00	622.00	1739.00	3040.00
80.	Apparent Power 2 (S)	330.00	389.00	1487.00	3241.00	4941.00	6949.00
81.	Power Factor 2 (PF)	0.61	0.62	0.94	0.98	0.94	0.90
82.	Frequency 2 (Hz)	49.93	49.88	49.85	49.87	49.90	49.92
83.	RMS Voltage 3 (V)	218.27	219.40	220.73	222.27	221.74	224.34
84.	RMS Current 3 (I)	2.03	4.56	7.69	14.41	24.16	31.94
85.	Active Power 3 (P)	260.00	856.00	1497.00	2889.00	4448.00	5709.00
86.	Reactive Power 3 (Q)	359.00	518.00	799.00	1381.00	2984.00	4330.00
87.	Apparent Power 3 (S)	443.00	1001.00	1697.00	3202.00	5357.00	7165.00
88.	Power Factor 3 (PF)	0.59	0.86	0.88	0.90	0.83	0.80
89.	Frequency 3 (Hz)	49.92	49.88	49.84	49.87	49.89	49.92
90.	Voltage THD 1 (%)	1.34	1.32	1.48	1.64	1.69	1.75
91.	Current THD 1 (%)	36.67	30.70	10.43	9.51	8.67	7.02
92.	Voltage THD 2 (%)	1.48	1.46	1.56	1.75	1.92	1.96
93.	Current THD 2 (%)	54.21	47.73	20.38	11.30	8.52	6.77
94.	Voltage THD 3 (%)	1.72	1.63	1.80	1.96	2.19	2.32
95.	Current THD 3 (%)	42.07	19.87	16.08	9.15	6.79	5.94
96.	PV Voltage (V)	404.13	334.27	383.39	355.89	384.42	378.54
97.	PV Current (I)	2.40	5.90	12.90	26.70	39.00	53.30
98.	Total Input PV Power (W)	960.00	1970.00	4930.00	9610.00	14970.00	20150.00
99.	Battery Voltage (V)	268.20	266.42	263.15	270.86	268.13	267.88
100.	Battery Current (I)	1.20	0.50	0.10	0.40	0.10	0.20
101.	Input dc Power (W)	310.00	130.00	20.00	110.00	20.00	50.00
102.	Efficiency (%)	44.58	75.02	84.16	87.34	88.58	87.83

Kamlesh
Tested By

Date.....



Issued By

Shruti

Date.....



Annexure - II

*Efficiency = Output Load / Input Power (Battery)

Table.1: Inverter Efficiency Test Standalone Mode Power Factor = 1 at battery voltage: 240 V

S.No.	Load %	5	10	25	50	75	100
1.	RMS Voltage 1 (V)	225.33	226.08	226.55	226.63	226.02	225.07
2.	RMS Current 1 (I)	1.44	2.91	7.23	14.44	21.65	28.75
3.	Active Power 1 (P)	324.29	656.77	1637.45	3272.76	4893.22	6470.13
4.	Reactive Power 1 (Q)	1.24	1.21	1.12	1.41	3.16	5.66
5.	Apparent Power 1 (S)	324.29	656.77	1637.45	3272.76	4893.22	6470.13
6.	Power Factor 1 (PF)	1.00	1.00	1.00	1.00	1.00	1.00
7.	Frequency 1 (Hz)	49.96	49.96	49.96	49.96	49.96	49.96
8.	RMS Voltage 2 (V)	232.33	231.06	231.25	232.19	232.56	232.69
9.	RMS Current 2 (I)	1.39	2.82	7.38	14.68	22.29	29.77
10.	Active Power 2 (P)	323.55	652.29	1706.62	3408.85	5184.02	6926.97
11.	Reactive Power 2 (Q)	1.44	1.40	0.87	1.41	4.00	6.00
12.	Apparent Power 2 (S)	323.56	652.30	1706.62	3408.85	5184.02	6926.97
13.	Power Factor 2 (PF)	1.00	1.00	1.00	1.00	1.00	1.00
14.	Frequency 2 (Hz)	49.96	49.96	49.96	49.96	49.96	49.96
15.	RMS Voltage 3 (V)	232.45	232.66	233.77	234.18	233.50	232.88
16.	RMS Current 3 (I)	1.49	2.99	7.01	14.34	22.44	29.96
17.	Active Power 3 (P)	346.07	696.53	1638.61	3358.22	5239.85	6977.22
18.	Reactive Power 3 (Q)	3.05	2.87	2.45	2.65	6.00	9.17
19.	Apparent Power 3 (S)	346.08	696.53	1638.61	3358.22	5239.85	6977.23
20.	Power Factor 3 (PF)	1.00	1.00	1.00	1.00	1.00	1.00
21.	Frequency 3 (Hz)	49.96	49.96	49.96	49.96	49.96	49.96
22.	Voltage THD 1 (%)	2.50	1.84	1.34	2.11	2.30	2.32
23.	Current THD 1 (%)	2.50	1.84	1.33	2.09	2.29	2.31
24.	Voltage THD 2 (%)	2.82	1.83	1.24	1.97	2.13	2.10
25.	Current THD 2 (%)	2.83	1.84	1.23	1.96	2.12	2.09
26.	Voltage THD 3 (%)	2.50	2.07	1.83	2.19	2.27	2.22
27.	Current THD 3 (%)	2.51	2.08	1.81	2.18	2.27	2.21
28.	Total AC output Power (W)	993.9	2005.6	4982.7	10039.8	15317.1	20374.3
29.	Battery Voltage (V)	243.27	243.55	243.30	242.99	242.55	242.77
30.	Battery Current (I)	5.60	10.00	22.70	44.60	68.10	91.00
31.	Input dc Power (W)	1360	2440	5530	10830	16530	22090
32.	Efficiency (%)	73.34	82.07	90.13	92.74	92.67	92.24

Kamlesh
Tested By

Date.....



Issued By

Date.....

[Signature]



Table.2: Inverter Efficiency Test Standalone Mode Power Factor = .8 at battery voltage: 240 V

S.No.	Load %	25	50	75	100
1.	RMS Voltage 1 (V)	225.04	225.53	224.15	224.42
2.	RMS Current 1 (I)	14.59	7.31	22.33	28.4145
3.	Active Power 1 (P)	2662.70	1332.49	4066.37	5070.55
4.	Reactive Power 1 (Q)	1921.73	972.28	2918.62	3866.71
5.	Apparent Power 1 (S)	3283.75	1649.50	5005.37	6376.67
6.	Power Factor 1 (PF)	0.81	0.81	0.81	0.7952
7.	Frequency 1 (Hz)	49.96	49.96	49.96	49.959
8.	RMS Voltage 2 (V)	230.76	230.91	230.51	230.53
9.	RMS Current 2 (I)	14.84	7.36	22.83	29.815
10.	Active Power 2 (P)	2696.76	1358.80	4191.02	5568.11
11.	Reactive Power 2 (Q)	2111.61	1021.37	3182.09	4029.57
12.	Apparent Power 2 (S)	3425.11	1699.86	5262.16	6873.23
13.	Power Factor 2 (PF)	0.79	0.80	0.80	0.8101
14.	Frequency 2 (Hz)	49.96	49.96	49.96	49.959
15.	RMS Voltage 3 (V)	231.43	232.29	230.37	231.17
16.	RMS Current 3 (I)	15.19	7.55	23.26	29.6108
17.	Active Power 3 (P)	2853.13	1415.10	4372.14	5453.33
18.	Reactive Power 3 (Q)	2052.04	1034.35	3097.53	4137.38
19.	Apparent Power 3 (S)	3514.43	1752.82	5358.20	6845.2
20.	Power Factor 3 (PF)	0.81	0.81	0.82	0.7967
21.	Frequency 3 (Hz)	49.96	49.96	49.96	49.959
22.	Voltage THD 1 (%)	2.92	2.36	2.90	2.925
23.	Current THD 1 (%)	2.28	1.94	2.32	2.304
24.	Voltage THD 2 (%)	2.87	2.52	2.77	2.624
25.	Current THD 2 (%)	2.26	2.31	2.21	2.029
26.	Voltage THD 3 (%)	3.06	2.66	2.95	3.001
27.	Current THD 3 (%)	2.39	2.53	2.35	2.345
28.	Total AC output Power (VA)	10223.29	5102.18	15625.73	20095.1
29.	Battery Voltage (V)	37.10	19.00	57.30	70.2
30.	Battery Current (I)	242.72	242.35	241.54	252.08
31.	Input dc Power (W)	9010.00	4610.00	13840.00	17690
32.	Efficiency (%)	91.18	89.05	91.25	90.96

Kamlesh
Tested By

Date.....



Issued By *[Signature]*
Date.....



Annexure - III

Islanding prevention measures for utility-interconnected photovoltaic inverters: IEC 62116											
No.	PEUT (%) of EUT rating)	Reactive load (% of Q_1)	P_{ac} (%) of nominal)	Q_{ac} (%) of nominal)	Run on time (ms)	PEUT (kW)	Actual Q_1 Phase A	Actual Q_1 Phase B	Actual Q_1 Phase C	P/DC	Remarks
1	100	100	0	0	290	20	1.014	1.006	1.010	397	Test A at BL*
2	66	66	0	0	291	6.6	1.002	1.006	1.006	343	Test B at BL
3	33	33	0	0	300	13.8	1.003	1.001	1.008	292	Test C at BL
4	100	100	-5	-5	306	20	1.002	1.104	1.180	397	Test A at IB
5	100	100	-5	0	260	20	1.206	1.114	1.118	397	Test A at IB*
6	100	100	-5	+5	266	20	1.223	1.118	1.190	397	Test A at IB
7	100	100	0	-5	246	20	1.032	1.001	0.991	397	Test A at IB
8	100	100	0	+5	282	20	0.997	0.956	0.947	397	Test A at IB
9	100	100	+5	-5	290	20	1.092	1.058	1.042	397	Test A at IB
10	100	100	+5	0	272	20	1.076	1.034	1.020	397	Test A at IB
11	100	100	+5	+5	258	20	1.046	1.007	0.990	397	Test A at IB
12	66	66	0	-5	279	13.8	1.145	1.117	1.192	343	Test B at IB
13	66	66	0	-4	293	13.8	1.168	1.107	1.203	343	Test B at IB
14	66	66	0	-3	283	13.8	1.144	1.093	1.207	343	Test B at IB
15	66	66	0	-2	268	13.8	1.140	1.072	1.168	343	Test B at IB
16	66	66	0	-1	271	13.8	1.128	1.082	1.191	343	Test B at IB
17	66	66	0	1	290	13.8	1.110	1.072	1.156	343	Test B at IB
18	66	66	0	2	252	13.8	1.108	1.077	1.196	343	Test B at IB
19	66	66	0	3	286	13.8	1.103	1.062	1.142	343	Test B at IB
20	66	66	0	4	292	13.8	1.137	1.051	1.154	343	Test B at IB
21	66	66	0	5	261	13.8	1.119	1.051	1.149	343	Test B at IB
22	33	33	0	-5	290	6.6	1.128	1.123	1.234	292	Test C at IB
23	33	33	0	-4	273	6.6	1.123	1.134	1.204	292	Test C at IB
24	33	33	0	-3	291	6.6	1.127	1.130	1.204	292	Test C at IB
25	33	33	0	-2	290	6.6	1.121	1.105	1.217	292	Test C at IB
26	33	33	0	-1	167	6.6	1.136	1.109	1.225	292	Test C at IB
27	33	33	0	1	300	6.6	1.121	1.113	1.194	292	Test C at IB
28	33	33	0	2	270	6.6	1.114	1.120	1.193	292	Test C at IB
29	33	33	0	3	260	6.6	1.107	1.109	1.166	292	Test C at IB
30	33	33	0	4	272	6.6	1.099	1.100	1.182	292	Test C at IB
31	33	33	0	5	251	6.6	1.107	1.092	1.180	292	Test C at IB

*BL: Balance Condition
 *IL: Imbalance Condition

Tested By
Kamlesh
 Date.....

Shuchi
 Issued By
 Date.....



Annexure - IV

Photovoltaic (PV) systems –Characteristics of the utility interface (CEI IEC -61727)		Remark																																								
4.4	<p>DC injection [The PV system shall not inject DC current greater than 1 % of the rated inverter output current, into the utility AC interface under any operating condition]</p>	Ok																																								
4.6	<p>Harmonics and waveform distortion [Total harmonic current distortion shall be less than 5 % at rated inverter output. Each harmonic shall be limited to the percentages listed in Table 1. Even harmonics in these ranges shall be less than 25 % of the lower odd harmonic limits listed]</p> <p style="text-align: center;">Table 1 – Current distortion limits</p> <table border="1" style="width: 100%;"> <thead> <tr> <th>Odd harmonics</th> <th>Distortion limit</th> <th>Max Measured Value ϕ_1</th> <th>Max Measured Value ϕ_2</th> <th>Max Measured Value ϕ_3</th> </tr> </thead> <tbody> <tr> <td>3rd through 9th</td> <td>Less than 4.0 %</td> <td>2.035 % @ 5th</td> <td>1.70 % @ 5th</td> <td>1.78 % @ 5th</td> </tr> <tr> <td>11th through 15th</td> <td>Less than 2.0 %</td> <td>0.359 % @ 11th</td> <td>0.29 % @ 11th</td> <td>0.44 % @ 11th</td> </tr> <tr> <td>17th through 21st</td> <td>Less than 1.5 %</td> <td>0.04 % @ 17th</td> <td>0.03 % @ 17th</td> <td>0.01 % @ 17th</td> </tr> <tr> <td>23rd through 33rd</td> <td>Less than 0.6 %</td> <td>0.005 % @ 31st</td> <td>0.009 % @ 31st</td> <td>0.05 % @ 31st</td> </tr> </tbody> </table> <table border="1" style="width: 100%;"> <thead> <tr> <th>Even harmonics</th> <th>Distortion limit</th> <th>Max Measured Value ϕ_1</th> <th>Max Measured Value ϕ_2</th> <th>Max Measured Value ϕ_3</th> </tr> </thead> <tbody> <tr> <td>2nd through 8th</td> <td>Less than 1.0 %</td> <td>0.141 % @ 2nd</td> <td>0.194 % @ 2nd</td> <td>0.122 % @ 2nd</td> </tr> <tr> <td>10th through 32nd</td> <td>Less than 0.5 %</td> <td>0.017 % @ 12th</td> <td>0.016 % @ 12th</td> <td>0.052 % @ 12th</td> </tr> </tbody> </table>	Odd harmonics	Distortion limit	Max Measured Value ϕ_1	Max Measured Value ϕ_2	Max Measured Value ϕ_3	3rd through 9 th	Less than 4.0 %	2.035 % @ 5 th	1.70 % @ 5 th	1.78 % @ 5 th	11th through 15 th	Less than 2.0 %	0.359 % @ 11 th	0.29 % @ 11 th	0.44 % @ 11 th	17th through 21 st	Less than 1.5 %	0.04 % @ 17 th	0.03 % @ 17 th	0.01 % @ 17 th	23rd through 33 rd	Less than 0.6 %	0.005 % @ 31 st	0.009 % @ 31 st	0.05 % @ 31 st	Even harmonics	Distortion limit	Max Measured Value ϕ_1	Max Measured Value ϕ_2	Max Measured Value ϕ_3	2nd through 8 th	Less than 1.0 %	0.141 % @ 2 nd	0.194 % @ 2 nd	0.122 % @ 2 nd	10th through 32 nd	Less than 0.5 %	0.017 % @ 12 th	0.016 % @ 12 th	0.052 % @ 12 th	Ok
Odd harmonics	Distortion limit	Max Measured Value ϕ_1	Max Measured Value ϕ_2	Max Measured Value ϕ_3																																						
3rd through 9 th	Less than 4.0 %	2.035 % @ 5 th	1.70 % @ 5 th	1.78 % @ 5 th																																						
11th through 15 th	Less than 2.0 %	0.359 % @ 11 th	0.29 % @ 11 th	0.44 % @ 11 th																																						
17th through 21 st	Less than 1.5 %	0.04 % @ 17 th	0.03 % @ 17 th	0.01 % @ 17 th																																						
23rd through 33 rd	Less than 0.6 %	0.005 % @ 31 st	0.009 % @ 31 st	0.05 % @ 31 st																																						
Even harmonics	Distortion limit	Max Measured Value ϕ_1	Max Measured Value ϕ_2	Max Measured Value ϕ_3																																						
2nd through 8 th	Less than 1.0 %	0.141 % @ 2 nd	0.194 % @ 2 nd	0.122 % @ 2 nd																																						
10th through 32 nd	Less than 0.5 %	0.017 % @ 12 th	0.016 % @ 12 th	0.052 % @ 12 th																																						
4.7	<p>Power factor [The PV system shall have a lagging power factor greater than 0. 8 when the output is greater than 50 % of the rated inverter output power.]</p>	Ok																																								
5.2.1	<p>Over/under voltage</p> <p style="text-align: center;">Table 2 – Response to abnormal voltages</p> <table border="1" style="width: 100%;"> <thead> <tr> <th>Voltage (at point of utility connection)</th> <th>Maximum trip time*</th> <th>Measured Value</th> </tr> </thead> <tbody> <tr> <td>$V < 0.5 V_{\text{nominal}}$</td> <td>0.1 s</td> <td>78 ms at 110 V</td> </tr> <tr> <td>$50 \% \leq V < 85\%$</td> <td>2.0 s</td> <td>290 ms at 160 V</td> </tr> <tr> <td>$85 \% \leq V < 110 \%$</td> <td>Continuous operation</td> <td>(190 < V < 273)</td> </tr> <tr> <td>$110 \% < V < 135 \%$</td> <td>2.0 s</td> <td>120 ms at 289 V</td> </tr> <tr> <td>$135 \% \leq V$</td> <td>0.05 s</td> <td>Not tested</td> </tr> </tbody> </table>	Voltage (at point of utility connection)	Maximum trip time*	Measured Value	$V < 0.5 V_{\text{nominal}}$	0.1 s	78 ms at 110 V	$50 \% \leq V < 85\%$	2.0 s	290 ms at 160 V	$85 \% \leq V < 110 \%$	Continuous operation	(190 < V < 273)	$110 \% < V < 135 \%$	2.0 s	120 ms at 289 V	$135 \% \leq V$	0.05 s	Not tested	Ok																						
Voltage (at point of utility connection)	Maximum trip time*	Measured Value																																								
$V < 0.5 V_{\text{nominal}}$	0.1 s	78 ms at 110 V																																								
$50 \% \leq V < 85\%$	2.0 s	290 ms at 160 V																																								
$85 \% \leq V < 110 \%$	Continuous operation	(190 < V < 273)																																								
$110 \% < V < 135 \%$	2.0 s	120 ms at 289 V																																								
$135 \% \leq V$	0.05 s	Not tested																																								
5.2.2	<p>Over/under frequency [When the utility frequency is outside the range of ± 1 Hz, the system shall cease to energize the utility line within 0. 2 s. The purpose of the allowed range and time delay is to allow continued operation for short-term disturbances and to avoid excessive nuisance tripping in weak-utility system conditions.]</p>	Range (47 - 53) Hz																																								
5.3	<p>Islanding protection The PV system must cease to energize the utility line within 2 s of loss of utility.</p>	See Annexure-III																																								
5.4	<p>Response to utility recovery Following an out-of-range utility condition that has caused the photovoltaic system to cease energizing, the photovoltaic system shall not energize the utility line for 20 s to 5 min after the utility service voltage and frequency have recovered to within the specified ranges.</p>	240 seconds																																								

Tested By
Kamlesh
Date.....




Issued By *Sharma*
Date.....



Annexure-VI

Environmental testing as IEC 60068-2-2 Dry heat test			
Sr. No	Requirement + Test	Result/Remarks	
1	Dry Heat Test	Pass	
1.1	Pre-check: examination before environmental conditioning	Pass	
1.1.1	Physical damages	No physical damages observed	
1.1.2	EUT working condition	AC Voltage 1/2/3 (V)- 225.06/ 232.68/ 232.94 V Total active Power (p)- 20387.2 Watt Frequency: 49.9 Hz Total DC Power - 22090 Watt	Pass

DRY HEAT TEST SPECIFICATION



1.2.1	EUT operating condition	Powered On	
1.2.2	Test temperature	+55°C	
1.2.3	One cycle duration	16 hours	
1.2.4	No. of cycles	1 cycle	
1.3	Post check: examination after environmental conditioning	Pass	
1.3.1	Physical damages	No physical damages observed	
1.3.2	EUT working condition	AC Voltage 1/2/3 (V)- 250/ 225.08 / 232.7 V Total active Power (p)- 20388.62 Watt Frequency: 49.9 Hz Total DC Power - 22090 Watt	Pass

Tested By
Kamlesh
Date.....




Issued By *[Signature]*
Date.....



Environmental testing as IEC 60068-2-1 cold Test

Sr. No	Requirement + Test	Result/Remarks
2	Cold Test	Pass

COLD TEST SPECIFICATION



2.1	EUT operating condition	Powered On	
2.1.2	Test temperature	-10°C	
2.1.3	One cycle duration	2 hours	
2.1.4	No. of cycles	1 cycle	
2.2	Post check: examination after environmental conditioning		Pass
2.2.1	Physical damages	No physical damages observed	Pass
2.2.2	EUT working condition	AC Voltage 1/2/3 (V)- 225.08/ 232.7/232.89 V Total active Power (p)- 20384.93Watt Frequency: 49.9 Hz Total DC Power - 22100 Watt	Pass

Tested By
Kambashi
Date.....




Issued By
Shuchi
Date.....



Environmental testing as IEC 60068-2-30 Damp Heat Cyclic Test		
Sr. No	Requirement + Test	Result/Remarks
3	Damp Heat Cyclic Test	Pass

DAMP HEAT CYCLIC TEST SPECIFICATION



3.1	EUT operating condition	Powered On	
3.1.1	Ramp-up / -down time	3 hours	
3.1.2	One cycle duration	12 hours + 12 hours	
3.1.3	No. of cycles	Two-cycle	
3.1.4	Total test duration	48 hours	
3.2	Post check: examination after environmental conditioning	Pass	
3.2.1	Physical damages	No physical damages observed	Pass
3.2.2	EUT working condition	AC Voltage 1/2/3 (V)- 225.07/ 232.69/ 232.88 V Total active Power (p)- 20372.21 Watt Frequency: 49.9 Hz Total DC Power - 22070 Watt	Pass

Tested By
Kamlesh
Date.....




Issued By
[Signature]
Date.....



Environmental testing as IEC 60068-2-14 Change of Temperature Test		
Sr. No	Requirement + Test	Result/Remarks
4	Change of Temperature Test	Pass

CHANGE OF TEMPERATURE TEST SPECIFICATION



4.1	EUT operating condition	Powered On	
4.1.1	Test Temperature	Upper : + 55°C Lower : - 10°C	
4.1.2	The rate of change of temperature	1°C/min	
4.1.3	Dwell Time	1 Hr. at each temperature	
4.1.4	No. of cycles	Five cycle	
4.2	Post check: examination after environmental conditioning		Pass
4.2.1	Physical damages	No physical damages observed	Pass
4.2.2	EUT working condition	AC Voltage 1/2/3 (V)- 225.07/ 232.69/ 232.89 V Total active Power (p)- 20377.73 Watt Frequency: 49.9 Hz Total DC Power - 22060 Watt	Pass

Tested By
Kamlesh
Date.....



Issued By
[Signature]
Date.....

Annexure-VII

Visual inspection of product

a. Front view (photograph)




b. Back view (photograph)



c. Side view (photograph)



d. Marking label (photograph)

PRODUCT - SOLAR PCU (SUNMAGIC+)		DAF 1801/02
SR. NO. - 2017052000	AC INPUT - 300 - 400 VAC	
RATING - 20 KW	AC OUTPUT - 400 VAC	
BATTERY DC - 240 VDC	FREQ - 50 HZ	
PV RANGE - 200 - 400 V	IMP. DATE - 08/01/2018	
PHOTO V.	IMP. DATE	
 ENERGYTECH UPS PVT. LIMITED S-30, 305 / 1-2, BHARADWAR, P.O. BHARADWAR, DIST. PUNE - 411 011 MOB - 9329292500, 9329252400 Email - support@energytech.com Web - www.energytech.com		

PRODUCT - SOLAR PCU (SUNMAGIC+)		DAF 1801/02
SR. NO. - 2017052000	AC INPUT - 300 - 400 VAC	
RATING - 20 KW	AC OUTPUT - 400 VAC	
BATTERY DC - 240VDC	FREQ - 50 HZ	
PV RANGE - 200 - 400V	IMP. DATE - 08/01/2018	
PHOTO V.	IMP. DATE	
 ENERGYTECH UPS PVT. LIMITED S-30, 305 / 1-2, BHARADWAR, P.O. BHARADWAR, DIST. PUNE - 411 011 MOB - 9329292500, 9329252400 Email - support@energytech.com Web - www.energytech.com		

Tested By
Kamlesh
Date.....



Issued By

Shuchi

Date.....

National Institute of Solar Energy

(An Autonomous Institution of MNRE, GOI)

Department of Solar, Gurgaon-Faridabad Road, Gwal Phari, Gurgaon (Haryana) - 122003

Customer Service Cell

Feed Back

Company Name:

Company Address:

Name of Person giving Feedback:

Designation & Location:

Sl. No.	Particulars	Feedback Ratings			
		Excellent*	Good	Average	Poor*
1	Content of Report				
2	Sample Handling				
3	Time Taken				
4	Test Report Format				
5	Courtesy				

*Please give comments:

Remarks:

Signature & Date of Client

(Name of Authorized Person)

For Official Use

Acknowledged by _____

Date _____

Mode: By Post/Hand/E-mail

T.A/T.M/E: